



### Project Highlights

- V-ROD® GFRP rebar cast in pre-cast pre-stressed concrete deck panels in area of approximately 275m L x 11m W.
- Pre-cast deck panels used #5 (16m) and #6 (19m) GFRP bar with #4 Carbon V-ROD for pre-stressing panels
- V-ROD® non-corrosive, durable and lightweight properties in precast provide greater quality control, simpler and quicker installation on site.

### Noden Causeway, ON summer 2008

- V-ROD Canada supplied V-ROD® GFRP/CFRP reinforcement for the Noden Causeway rehab project in Fort Francis area.
- Owner: Ministry of Transportation - NW Region
- Contractor: Sparcon/Lafarge pre-cast/Harris Rebar
- Engineer: Cook Engineering/MTO